

Addendum #1

The following changes and clarifications shall be incorporated into the plans and specifications dated September 8, 2022 for the UCCS Replace AHU and RA System Columbine Hall.

Specifications:

Section 23 63 33:

REPLACE Section 1.4.E. with:

"E. Evaporative cooled condensing unit coils shall be leak tested at 150 psig, and pressure tested at 350 psig."

REPLACE Section 2.1.A. with:

"A. Evaporative Cooled Condensing Unit"

REPLACE 2.2 with:

"2.2 EVAPORATIVE COOLED CONDENSING UNIT"

Drawings:

Sheet M-12:

CHANGE plan 2 sheetnote #8 at the sight glass from sheetmore #8 to sheetnote #9 and DELETE "(TYP)".